## LIEBERT® NXL™ 250-400kVA, 1+1 (DISTRIBUTED BYPASS) MULTI-MODULE SYSTEM SITE PLANNING DATA

Table 1 Site planning data—250-400kVA

UPS Rating		AC Input/	Input	Rectifier AC Input Current		Bypass/Output AC Output Current	Maximum Battery	Maximum Heat Dissipation Full	Dimensions	Approximate
kV A	kW	Output Voltage, VAC	Isolation Transformer	Nom	Max	Nom	Current at End of Discharge (A)	Load, BTU/h (kW)	WxDxH, in. (mm)	Weight Unpacked, lb. (kg)
250	225	480	NO	312	389	301	615	53,592 (15.7)	71.8x33.5x76.8 (1823x850x1950 )	3965 (1798)
250	225	575		260	326	251		53,662 (15.7)	78.5x33.5x76.8 (1993x850x1950 )	4975 (2257)
250	225	600		250	312	241				
300	270	480		371	464	361	730	61,890 (18.1)		4840 (2195)
300	270	575		308	386	301		64,100 (18.8)		5440 (2468)
300	270	600		296	369	289				
400	36 0	480		497	621	481	980	74,173 (21.7)	78.5x39.4x76.8 (1993x1000x195 0)	6280 (2849)
400	36 0	575		419	524	402	990	86,265 (25.3)	114.5x39.4x76.8 * (2908x1000x195 0)	6925 (3141)
400	36 0	600		401	502	385				
See Notes below:         —         1,3,6,7,8,10,11						2,3,4,6,7,8,10,11	5,6,8,10,11	_	9	9

<sup>\*</sup> Deduct 16.1 inches (409mm) when battery cabinets are attached.



## Notes for Table 1


- Nominal rectifier AC input current (considered continuous) is based on full rated output load. Maximum current includes nominal input current and maximum battery recharge current (considered non-continuous). Maximum input current is controlled by current limit setting which is adjustable 25 to 125% of nominal input current.
- 2. Bypass AC input and AC output current (considered continuous) is based on full rated output load.
- 3. Vertiv recommends that feeder protection (by others) for the rectifier AC input and the bypass AC input be provided by separate overcurrent protection devices.
- 4. UPS output load cables must be run in separate conduit from input cables.
- 5. Power cable from module DC bus to battery should be sized for a total maximum 2.0V line drop (power cable drop plus return cable drop as measured at the module) at maximum discharge current.
- 6. Grounding conductors to be sized per NEC 250-95. Neutral conductors to be sized for full capacity per NEC 310-16, Note 10 for systems with 4-wire loads and 20% minimum capacity for 3-wire loads.

- NOTE: A neutral conductor is required from each Multi-Module Unit output to the System Switch Board.
- Rectifier AC Input: 3-phase, 3-wire, plus ground Bypass AC Input: 3-phase, 4-wire, plus ground (3-wire plus ground in certain circumstances)
  - AC Output to Load: 3-phase, 3- or 4-wire, plus ground Module DC Input from Battery: 2-wire (positive and negative), plus ground Module Output to SPC: 3-phase, 4-wire, plus ground
- 8. All wiring is to be in accordance with National and Local Electrical Codes.
- 9. Minimum overhead clearance is 2 ft. (0.6m) above the UPS.
- 10. Top or bottom cable entry through removable access plates. Cut plate to suit conduit size.
- 11. Control wiring and power cables must be run in separate conduits. Control wiring must be stranded tinned conductors.
- 12. Dimensions and weights do not include the System Paralleling Cabinet.
- 13. For optimal load sharing performance, the difference in bypass circuit cable length must be 10% or less from longest to shortest. Cable length should be measured from common point of input to common point of output. If needed, contact your Vertiv representative to determine if other lengths are be acceptable.

VertivCo.com | Vertiv Headquarters, 1050 Dearborn Drive, Columbus, OH, 43085, USA

© 2018 Vertiv Co. All rights reserved. Vertiv and the Vertiv logo are trademarks or registered trademarks of Vertiv Co. All other names and logos referred to are trade names, trademarks or registered trademarks of their respective owners. While every precaution has been taken to ensure accuracy and completeness herein, Vertiv Co. assumes no responsibility, and disclaims all liability, for damages resulting from use of this information or for any errors or omissions. Specifications are subject to change without notice.

SL-25527\_REV2\_8-18



The Liebert NXL is compatible with high resistance ground systems. See your local Vertiv representative for details.

Liebert <sup>®</sup> NXL <sup>™</sup> 250-400kVA, 1+1 (Distributed Bypass) Multi-Module System Site Planning Data					